

Section 64 – Erosion Control

Plans for storm water conveyance systems shall include appropriately designed temporary and permanent erosion-control measures for the open channel structures and all de-vegetated land draining to both open and closed conduits within the system. (Refer to Best Management Practice for Construction Activities prepared by the Kentucky Natural Resources and Environmental Protection Cabinet – should be used as a design manual for erosion and sediment control.)